VegPro scouting — what we need from IT to go live

To: Mohammed Khaja Imran, VegPro IT

From: Kalpit Patel

Date: 5 October 2026

Server: FDB (`192.168.16.14`)

Database: Microsoft SQL Server, database **Scouting** (already created)

This note answers the request for a full list before the scouting website goes online. The website name (domain) is **not chosen here**. VegPro IT will provide that name. The certificate and DNS must use the name IT provides.

The application is already installed on FDB. What remains is the company website address, a trusted HTTPS certificate, and IIS so the site stays up after a reboot.

Already done on FDB

- Node.js is installed.
- The application is in `C:\Users\Scouting\Veg-pro-Smart-Farms-master`.
- Database **Scouting** exists. The application tables and the three demo logins are loaded.
- The application connects with the Windows account **FDB\Scouting** (Windows authentication). It does not use a SQL password login.
- Photos are stored on disk at `C:\Users\Scouting\Veg-pro-Smart-Farms-master\data\evidence`.
- A temporary test address works only while two Command Prompt windows are left open. That is not the live setup.

No Supabase and no PostgreSQL are used on FDB.

What we need from IT

1. The website name

Please provide the hostname staff and scouts will open in the browser. Example shape only: a name on a domain VegPro already owns. We will not invent one.

That same name must be:

- The name on the HTTPS certificate
- The name in internal DNS
- The address printed for scouts

2. Internal DNS

On the VegPro network (office and farm Wi-Fi), that hostname must resolve to **192.168.16.14**.

Phones must reach FDB by that name. They must not be sent to the public internet for this site.

3. Trusted HTTPS certificate

Scouts' phones need a real HTTPS certificate. GPS does not work on a plain `http://` address, and a self-signed certificate makes Chrome show "Your connection is not private."

Please issue a certificate for the hostname from item 1, from the company certificate authority or a public authority the phones already trust.

Please provide:

- The certificate as a `.pfx` file (or install it in the Local Computer certificate store on FDB)
- The `.pfx` password, given in person or by a secure channel, not in a wide email
- Confirmation that farm phones and PCs trust the authority that signed it

4. IIS on FDB

IIS is **not** installed today. Please install, on FDB:

- Web Server (IIS), including IIS Management Tools
- URL Rewrite
- Application Request Routing (ARR), with the proxy enabled

IIS should listen on **HTTPS port 443** and forward all traffic to the Node.js application on this machine at `http://127.0.0.1:3000`.

IIS does not replace Node.js. Both must run. IIS only presents HTTPS. Node.js runs the website.

5. Keep the website running after reboot

The Node.js process must start when FDB starts, without someone logging in and opening a Command Prompt.

- Command: `npm run start`
- Working directory: `C:\Users\Scouting\Veg-pro-Smart-Farms-master`
- Windows account for that task: **FDB\Scouting**

It must be **FDB\Scouting**. The database login is that Windows account. If the task runs as another user, the site cannot open the Scouting database.

IIS should start on its own as a Windows service, which it normally does.

6. Firewall

Port	Who needs it	Action
443	Scout phones and PCs on the VegPro network	Allow to FDB
3000	This server only (IIS talks to Node.js locally)	Do not publish to the network if 443 is in place
1433	SQL Server, already used on the server	Do **not** publish to the internet

---

What we do not need

- A new SQL Server or a new database. **Scouting** on FDB is the database.
- Supabase, PostgreSQL, or a cloud database.
- The SQL password login. Windows authentication as **FDB\Scouting** is the working login.
- The site exposed on the public internet, unless VegPro later decides that. Farm Wi-Fi plus HTTPS is the requirement for go-live.
- Port 1433 opened to the internet.

How the live site will be checked

After the hostname, certificate, DNS, and IIS are in place:

1. On farm Wi-Fi, open `https:///auth/login`.
2. The browser shows a padlock, with no certificate warning.
3. Sign in as `worker@vegpro.com` / `VegPro2026!` and reach the worker home page.
4. Start a scouting walk and save a stop.
5. Sign in as `manager@vegpro.com` / `VegPro2026!` and see that stop.
6. Restart FDB and confirm the site comes back without anyone opening a Command Prompt.

The three demo passwords should be changed after go-live.

Reply we need from IT

Please send:

1. The hostname you will use
2. Who will create the certificate, and when the `.pfx` (or the installed certificate) will be ready
3. Confirmation that internal DNS will point that hostname to `192.168.16.14`
4. Confirmation that IIS, URL Rewrite, and ARR can be installed on FDB
5. Confirmation that a startup task can run `npm run start` as **FDB\Scouting**
6. Confirmation that TCP **443** will be allowed from the farm network to FDB, and that TCP **1433** will not be published to the internet